



Large Boat House Spray Insulation



Authorised Installer



Location



Project Type



Install Date

Green Horizon Energy Solutions Ltd	Clifton Cruises National	Insulation of large narrow boat	June 2024
------------------------------------	--------------------------	---------------------------------	-----------



Product Used



Product Category



Install Size



Install Duration

Heatlok HFO Pro	Closed Cell Spray Foam	75m ²	6 hours
-----------------	------------------------	------------------	---------

Project Overview:

Clifton cruisers, have several installs per year. This one was the biggest Boat House they have constructed.

HBS Authorised contractor, Green horizon Energy Solutions, were called to insulate this and another narrow boat in two days, the boat builders Clifton cruisers where extremely impressed by our work and said that it far surpassed the quality they had previously been getting, so much so that they will be using us again for future boats.

Closed cell foam was applied to roughly 40mm depth, all studs were taped up to prevent overspray and any excess foam was trimmed flush so the foam could be boarded over soon after application.

